

# Commercial Building Utilises GCP Technologies' Solution to Provide Durability

STRUX<sup>®</sup> 90/40, Eclipse Floor<sup>®</sup> and ADVA<sup>®</sup> 140M were crucial to creating a durable concrete floor.

---



<b>Project</b>	Safeguard Building Products Manufacturing Plant
<b>Owner</b>	Safeguard Building Products, Hattiesburg MS
<b>Concrete Supplier</b>	Southeastern Concrete Company, Hattiesburg MS
<b>Contractor</b>	Cajun Concrete Services Inc., Boutte LA
<b>GCP Solutions</b>	STRUX <sup>®</sup> 90/40 macro fibres, Eclipse <sup>®</sup> concrete admixture, ADVA <sup>®</sup> mid-range water reducer

## The Overview

### The Project

In the southeastern U.S. and especially the Gulf Coast region, high winds and wet weather can wreak havoc on wood homes. Driven by the increased demand for more durable homes, Andrew Marshall, owner of Safeguard Building Products, needed a new commercial building plant for manufacturing his company's metal studs and wind-resistant metal homes.

---

*"We're really happy the way this concrete has performed – the cost of the admixtures was definitely worth the expenditure. That's important when you're looking at the numbers – this admixture in lieu of steel and the labour costs of placing steel definitely worked out in the plus. The whole admixture worked like a champ. The pumpability, the consistent slumps, the set times – everything went according to spec and I think the owner's going to be thrilled with the longevity of the floor", said Harry LeBlanc of Cajun Concrete Services Inc."*

---

Andrew Marshall, Owner, Safeguard Building Products

## The Challenge

The challenge was that the new facility needed a high performance floor that would stand up to the rigours of busy operation. To ensure he got a durable concrete floor that would minimise shrinkage and cracking, Marshall turned to Doug Lambeth at Southeastern Concrete Company.

Drawing on his years of experience working with admixtures, Lambeth proposed an innovative concrete mix that would provide the results Marshall wanted—without the need for costly rebar or wire mesh reinforcement. He contacted GCP Applied Technologies for help. They, alongside the Engineering Services Group, worked with the owner's structural engineer to help put any doubts to rest. To design the optimal mix, the team also relied on GCP's Slab On Ground Software—a valuable tool that helped determine the best dosages for the 2,500-yard (2,286-metre) concrete pour.



## The Solution

The specialised 4,000 p.s.i. mix included GCP's STRUX® 90/40 synthetic macro fibre reinforcement, an alternative to rebar or welded wire mesh, that maximises crack control, fatigue resistance and durability. In addition, Eclipse® Floor shrinkage reducing concrete admixture was added to minimise shrinkage and cracking during drying and enable extended joint spacing, and ADVA® 140M was used as a mid-range water reducer for pumpability and workability.

“I really thought the heavy dose of fibre in the mix was going to be a problem from a pumpability standpoint, but it didn't cause us any grief at all”, said the contractor, Harry LeBlanc of Cajun Concrete Services. “We pumped and finished the concrete just the way it was all planned out on paper”.

The commercial building floor was finished with a laser screed, cut the same day, and covered with a vapour barrier after placement for seven days to maintain the desired moisture level.

## The Results

“Even with our early entry soft cut sawing, we didn’t see any cracking at all”, added LeBlanc. “I thought that was pretty phenomenal”.

The extended spacing also meant lower labour costs for the commercial building since fewer joints needed to be cut and maintained.

“It’s just a great mix to pour”, noted Marshall. “We got set times that were totally accurate, the performance we needed, and the mix enabled us to extend control joints to as far as 25 feet [7.6 metres] which worked better with our column spacing and helped our design team”.

In fact, the owner was so pleased with the hard work of everyone on the job, that at the end of each workday, he had a barbecue to feed everyone on the site.

Asked whether he’d use the mix design in the future, Marshall responded simply, “I don’t think I’d pour concrete again without it. That’s how well I think it performed”.

Blue360<sup>SM</sup> Product Performance Advantage: Because every project, large or small, deserves the best level of protection.

[th.gcpat.com](http://th.gcpat.com) | Thailand customer service: 66 2 030 9700

This document is only current as of the last updated date stated below and is valid only for use in Thailand. It is important that you always refer to the currently available information at the URL below to provide the most current product information at the time of use. Additional literature such as Contractor Manuals, Technical Bulletins, Detail Drawings and detailing recommendations and other relevant documents are also available on [www.th.gcpat.com](http://www.th.gcpat.com). Information found on other websites must not be relied upon, as they may not be up-to-date or applicable to the conditions in your location and we do not accept any responsibility for their content. If there are any conflicts or if you need more information, please contact GCP Customer Service.

Last Updated: 2018-08-27

[th.gcpat.com/about/project-profiles/commercial-building-utilizes-gcp-technologies-solution-provide-durability](http://th.gcpat.com/about/project-profiles/commercial-building-utilizes-gcp-technologies-solution-provide-durability)